

## Construction Set, Underwater

SC: 4220-95-E20  
NSN: 4220-01-473-0587  
LIN: W67980

### System Description

The Underwater Construction Set (UCS) consists of separate modules. Box 1 contains a hydraulic tool package used for construction/debris removal and cutting concrete, wood and metal. Box 2 contains a cutting and welding package used for surface or underwater operations. Box 3 contains a salvage package used for lifting heavy debris and recovering objects up to 160,000 lbs. Box 4 contains hand tools, hardware, and equipment used to survey, and mark underwater obstacles. The UCS set provides dive teams the capability to perform hydrographic surveys, obstacle emplacement and or reduction, assessment of battle damage and repair to water front facilities, bridges, dams, vessels, and support for river-crossing sites.

### Reset Responsibility

Unit

### Reset Location

This system is not currently in reset.

**This system is not currently in reset.**

### Reset Type

**Reset Work (Field Level)** - Work performed to correct equipment faults that are performed at the ORG/DS level; performed by unit level soldiers, augmented by contractor as required.

### Reset Strategy

n/a

### Reset Procedures

- Replace worn, broken, missing components IAW supply catalog.
- Reorder consumables IAW SC.

### **- Contact Information -**

877.4.PMSKOT (877.476.7568)  
[rock-pm-skot@conus.army.mil](mailto:rock-pm-skot@conus.army.mil)